

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21259-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 18-34S-24W
400 feet from S Section Line, 400 feet from W Section Line
Lease Name: KLINGER Well #: 1
County: CLARK Total Vertical Depth: 5900 feet

Operator License No.: 33384
Op Name: HIGH BLUFF OPERATING LLC
Address: 1732 WAZEE ST., STE. 204
DENVER, CO 80202

CIBP Size: feet: 5500 WITH 2 SX CMT
COND Size: 20 feet: 60
PROD Size: 4.5 feet: 5895 WITH 200 SX CMT
SURF Size: 8.625 feet: 811

#19175

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/27/2004 11:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: SHINE OVERBY Company: HIGH BLUFF OPERATING Phone: (303) 295-2223

Proposed Plugging Method: CIBP @ 5500' WITH 2 SX CMT. PLUG AT 830' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 04/27/2004 12:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 5500' WITH 2 SX CMT. PULL CASING OUT OF HOLE. 1ST PLUG RUN TUBING TO 830'. LOAD HOLE WITH WATER. SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 430'. SPOT 40 SX CMT. 3RD PLUG PULL TO 30' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5580	5612		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3850' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed _____

INVOICED

DATE 4-5-04
INV. NO. 200406498

(TECHNICIAN)

Form CP-1