

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03277-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 10-10S-25W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ELRICK UNIT Well #: 12-1
County: GRAHAM Total Vertical Depth: 4030 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

PROD Size: 5.5 feet: 4029 125 SX CMT
SURF Size: 8.625 feet: 209 115 SX CMT

\$130⁹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2004 9:30 AM

Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.

Proposal Rcvd. from: JEFF LEWIS Company: CITATION OIL & GAS CORP. Phone: (405) 681-9400

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 15 sxs gel spacer.
DV at 2186' set with 100 bbls Kempac.
CIBP at 3700'.
Well squeezed and TOC at 3520'.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/26/2004 3:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 1300' and 2200'.
TIH with tubing - hit TOC at 3520' - pulled up 10' - mixed and pumped 15 sxs gel.
Pulled up to 2300' - spotted 100 sxs cement.
Pulled up to 1200' - circulated cement with 115 sxs cement.
Topped with 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Hooked up to the annulus and pumped 15 sxs cement.
Max. P.S.I. 300#.

Top	Bot	Thru	Comments
3880	5015		

RECEIVED
MAY 05 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS KNOLL B-1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 5-3-04
INV. NO. 2004061490

Form CP-2/3

MAY 03 2004

EMPIRE DRLG CO

#1 KNOLL 'B'

10-10-25W
SW SW NE

Contr. EMPIRE DRLG

GRAHAM County

E 2532RB Comm.

Comp. 11-22-57

IP 251 BOPD/LANS
PHY POT

Tops	Depth	Datum
ANH	2162	370
TOP	3547	-1015
HFFB	3763	-1231
TOR	3785	-1253
LANS	3799	-1267
TD	4030	-1498

Casing CORRECTED CARD
8" 209 4-11-58
5" 4029 CORRECTED TOPS
& DST'S
DST 3770-98/30", 25' MUD, BHP 1180
DST 3794-3825/1 HR, 105' MDY SW, BHP
1120
DST 3825-40/1 1/2 HR, G/25", FLO 0/59
BHP 1390
DST 3840-55/1 HR, 2485' SW, BHP 1360
DST 3876-85/1 HR, 2200' G, 60' VH MCO,
60' MDY o, 120' CL GSY o, 60' SW,
BHP 1240
ELRICK NE POOL DST 3926-45/40", G/27",
o/34", BHP 1390
DST 4022-30/1 HR, 20' M,
BHP 0#: PERF 4004-08
ACID 3000: SWB 30 BOPD

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS