

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15453-00-00
Spot: S2SESW Sec/Twnshp/Rge: 5-18S-12W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: EVELEIGH B Well #: 2
County: BARTON Total Vertical Depth: 3348 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

PKR Size: 0 feet: 0
PROD Size: 5.5 feet: 3345 100 SX CMT
SURF Size: 8.625 feet: 250 160 SX CMT

108 8/

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2004 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN ART ROLO Company: NADEL AND GUSSMAN, LLC Phone: (913) 434-2916

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 20 sxs gel - 700# hulls.
Perf at 1306'. Perf anhy at 726'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2004 10:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 3400'+.
Spotted 20 sxs gel, followed with 35 sxs cement with 200# hulls mixed in cement.
Pulled to 1300' - spotted 100 sxs cement with 300# hulls.
POOH. Squeezed casing with 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
8 5/8" squeezed with 50 sxs cement with 200# hulls.
Max. P.S.I. 700#. S.I.P. 500#.

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

5-5-04

INV. NO.

2004061506

Form CP-2/3

APR 21 2004

NADEL & GUSSMAN #2 EVELEIGH 'B' 5-18-12W 53
 S2 SE SW

Contr. JONES DRLG BARTON County

E1810 RB Comm. Comp. 3-17-61 IP 202 BOPD

Tops	Depth	Datum
ANH	704	+1106
HEEB	2983	-1173
TQR	3002	-1192
BR LM	3084	-1274
LANS	3098	-1288
B/KC	3328	-1518
ARB	3344	-1534
TD	3348	-1538

Casing

8" 250
 5" 3345

DST 2989-3015/30", 15' M, BHP 1075-790//
 DST 3102-35/30", 10' SL OCM, BHP 595-0//
 DST 3135-75/1 HR, 120' G, 10' SL OCM,
 BHP 140-65//
 DST 3346-48/90", 240' G, 150' CL O, BHP
 1010-910//
 OO TD: SWB | BOPH, NATL: ACID 500: SWB
 5½ BOPH/6 HRS

REDWING SE POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

4390.01