

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20940-00-00  
Spot: N2SESW Sec/Twnshp/Rge: 1-9S-17W  
990 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: HRABE Well #: 6  
County: ROOKS Total Vertical Depth: 3490 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 4.5 feet: 3488 w/200 sxs cmt  
SURF Size: 8.625 feet: 204 w/150 sxs cmt

#113<sup>43</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2004 1:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 250 sxs Swift Multi-Density Cement - 500# hulls.  
Fluid level 2900'. PBTd 3490'. Perfs 3155' - 3438'.  
No records of squeezes.  
Perf Anhy at 1275'. Dakota at 725'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/27/2004 2:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 185 sxs Swift Multi-Density Cement with 500# hulls.  
Max. P.S.I. 200#. S.I.P. 0#. Hole full.  
Hooked up to backside - pumped 5 sxs Swift Multi-Density.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3434	3438		
3326	3334		
3302	3306		
3296	3298		
3282	3288		
3219	3222		
3173	3176		
3155	3160		

RECEIVED  
MAY 03 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

*Richard Williams*

INVOICED

(TECHNICIAN)

DATE

5-5-04

INV. NO.

2004061505

Form CP-2/3

APR 29 2004

MURFIN DRILLING COMPANY  
 617 UNION CENTER BLDG. #6 HRABE "A" 1-9-17W  
 WICHITA, KANSAS 67202 C N/2 SE SW  
 CONTR MURFIN DRLG. CO. CTY ROOKS

GEOL \_\_\_\_\_ FIELD WESTHUSIN

E 1984 KB CM 7/5/79 CARD ISSUED 9/29/79 IP P 192 BOPD  
 LANS 3155-3306 OA

+	+	+
+	+	+

API 15-163-20,940

LOG	TOPS	DEPTH	DATUM
SC		1268	+ 716
TOP		2860	- 876
HEEB		3078	-1094
TOR		3099	-1115
LANS		3119	-1135
BKC		3364	-1380
ARB		3425	-1441
LTD		3490	-1506

8-5/8" 204/150sx, 4 1/2" 3488/200sx  
 DST (1) 3107-3215/45-60-45-60, REC  
 270' OC&WCM, SIP 485-485#, FP 101-  
 201#  
 DST (2) 3218-3245/45-45-45-45, REC.  
 15' M W/SO, SIP 128-174#, FP 46-55#  
 MICT -CO, PF 3434-3438, SWB LD, SET  
 BP @ 3410, SET RBP @ 3323, AC 500 GAL,  
 SWB PT LD W/SO&M, AC 250 GAL, SWB LD &  
 TR OIL, PF (LANS) 3302-3306, 3296-  
 3298, 3219-3222, 3173-3176, 3155-3160,  
 AC 3200 GAL, SWB 16 BO/2HRS, POP, P  
 192 BOPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

1984 KB CM 7/5/79  
 CARD ISSUED 9/29/79  
 IP P 192 BOPD  
 LANS 3155-3306 OA