

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01774-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 34-9S-20W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DARRELL Well #: 2  
County: ROOKS Total Vertical Depth: 3827 feet

Operator License No.: 32158  
Op Name: H & B PETROLEUM CORP.  
Address: 520 S. HOLLAND, SUITE 307  
WICHITA, KS 67209

CIBP Size: feet: 3750  
PROD Size: 5.5 feet: 3823 100 SX CMT  
SURF Size: 8.625 feet: 1759 750 SX CMT

124<sup>38</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2004 11:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM CORP. Phone: (620) 564-3002

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 10% gel - 700# hulls.  
Hole in casing at 1000'.

Plugging Proposal Received By: DENNIS HAMEL  
Date/Time Plugging Completed: 04/22/2004 1:30 PM

Witness Type: COMPLETE (100%)  
KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 3710' - pumped 200 sxs cement with 200# hulls.  
Pulled to 1500' - pumped 60 sxs cement with 100# hulls.  
Circulated to surface.  
POOH with tubing and squeezed casing with 190 sxs cement.  
Cement circulated out of 8 5/8" x 5 1/2" annulus.  
Shut in same and squeezed casing/s.p. to Max. P.S.I. 700#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3823	3827	OH	

RECEIVED  
MAY 03 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Dennis L. Hamel*

(TECHNICIAN)

INVOICED

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_

APR 29 2004

GULF OIL CORPORATION #2 DARRELL 34-9-20W 22  
 NE NW NW

Contr. \_\_\_\_\_ ROOKS County

E. 2264 Comm. 4-19-50 Comp. 6-9-50 IP: 3000 BOPD  
 DRAW DOWN

Tops	Depth	Datum	Casing
ANH	1752	+ 512	8" 1759
HEEB	3486	- 1222	5" 3823
TOR	3511	- 1247	
LANS	3526	- 1262	
ONG	3783	- 1519	
SIMP	3807	- 1543	
ARB	3822	- 1558	
T.D.	3827	- 1563	

DP 3825: SWB 20 BO/4 HRS  
 ACID 200: 161 BO/8 HRS:  
 DD 3827: 173 BO/4 HRS:  
 ACID 500:  
 SWB 217 BO/4 HRS:

PALCO POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS