

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01617-00-00
Spot: S2NENW Sec/Twnshp/Rge: 10-9S-19W
990 feet from N Section Line, 1980 feet from W Section Line
Lease Name: ROSTICAL C Well #: 3
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

PROD Size: 5.5 feet: 3443 w/150 sxs cmt
SURF Size: 8.625 feet: 329 w/175 sxs cmt

8/11/96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2004 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Perforations: 3196' - 3396'. Squeezed off (2-81). Collapsed 5 1/2" casing at 2733'.
Plugging Arb. 3443'-3445'. OH squeezed with 65 sxs.
Method: PBSD 2928'. Unable to get below 1285'.
Squeezed Dakota 3-55 at 1080' w/165 sxs; 06-74 at 580' w/100 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2004 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 1275'.
Swift Services pumped 145 sxs Swift Multi-Density cement with 500# hulls - cement circulated.
Tubing stuck - backed off 19 joints. Left 22 joints in hole.
Swift Services pumped 58 sxs down 5 1/2" casing.
Max. P.S.I. 450#. S.I.P. 100#.
Hooked up to 8 5/8" and pumped 22 sxs cement.
Max. P.S.I. 200#. S.I.P. 75#.
04-28-2004 - Topped off with 15 sxs Multi-Density Cement - hole full.

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

HD

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 5-5-04

INV. NO. 2004061494

APR 29 2004

SONIO PETROLEUM COMPANY #3

ROSTICAL 'C'

10-9-144
S2 NE NW

Contr

ROOKS Counts

2041 RR Comm

Comp 11/15/62

IP 52 BOPD • 306 MTR

GR 31.50/LANS 3196-3396

UCD Tags	Depth	Datum
AMHY	1448	-593
NEEB	3159	-1118
LANS	3197	-1156
ARB	3442	-1401
TD	3443	-1404

Casing
 8" 329
 5" 3443:
 WAS: SAME OPR, ARB PROD 9/1/50;
 NEW INFO: PB: PERF
 RB: PERF 3196-3200; 3217-21; 3237-
 43; 3260-64; 3296-99; 3331-34;
 3337-40; 3351-54; 3393-96;
 3368-72:

MONOTIME

1	1	1
1	1	1
1	1	1
1	1	1

INDICATED BY A GAS SERVICE
 ORIGINAL SERVICE