

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-02014-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 36-20S-12W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DANNEBOHM Well #: 8
County: BARTON Total Vertical Depth: 3440 feet

Operator License No.: 4184
Op Name: CASINO PETROLEUM CO.
Address: PO BOX 415
ELLINWOOD, KS 67526

PROD Size: 4.5 feet: 3348
SURF Size: 8.625 feet: 252

\$1 111⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2004 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREW Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 265-4651

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 10% gel and hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 04/27/2004 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 300' - 580' - 1400'.
Casing collapsed or junk in hole at 1600'.
Ran tubing to 1400' and circulated with 60 sxs 60/40 pozmix - 10% gel cement.
POOH.
Pumped 50 sxs cement down backside.
Tied onto 4 1/2" and pumped 60 sxs cement.
Pumping into at 400# P.S.I. - blew hole in surface casing.
Cement started coming up outside at surface pipe.
Topped off with 25 sxs cement.

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 5-5-04
INV. NO. 2004061491

APR 30 2004

PETROLEUM INC

#8

DANNEBOHM

36-20-12W

NW NW SW 53

Contr.

BARTON

County

E. 1832 RB. Comm.

Comp. 1-7-55

IP 25 BOPD

Tops	Depth	Datum
Aw	595	+1237
HEEB	3014	-1182
BR LM	3146	-1314
LANS	3159	-1327
SIMP	3380	-1548
ARB	3387	-1555
TD	3440	-1608

Casing

8" 252

4" 3348

DST 3388-89/1 HR, 550' FREE OIL, BHP 850#

PERF 21/3387-97: ACID 500 5 1/2 BOPH:

CHASE-SILICA POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS