

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03240-00-00
Spot: NESWSW Sec/Twnshp/Rge: 10-10S-25W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ELRICK UNIT Well #: 7-3
County: GRAHAM Total Vertical Depth: 4015 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

PROD Size: 5.5 feet: 4014 100 SX CMT
SURF Size: 8.625 feet: 186 115 SX CMT

\$130⁴⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2004 9:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JEFF LEWIS Company: CITATION OIL & GAS CORP. Phone: (405) 681-9400

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 500# hulls.
DV at 2219' circulate with 100 bbls Kempac.
CIBP at 3690' and 3710' (leaking).
Hole in casing at 2523'.
Perf at 2300' - 2301' (2 holes).

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2004 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing - 3690'.
Spotted 20 sxs cement with 50# hulls - displaced with water and pulled to 3500'.
Spotted 15 sxs gel (29 bbls gelled water) - displaced with water and pulled to 2250'.
Perfed casing at 2300' - spotted 100 sxs cement - displace with water and pulled to 1300'.
Perfed casing at 1300' - spotted 150+ sxs cement to circulate at surface.
POOH with tubing and load and squeezed casing with 25+ sxs cement and squeezed to Max. P.S.I. 500#.
Tied onto 8 5/8" x 5 1/2" casing. Squeezed with 25+ sxs cement to Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3792	3995		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS DINKEL B-3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

4-5-04

INV. NO.

2004061490

Form CP-2/3

APR 29 2004

EMPIRE DRLG & N C R A

#3 DINKEL 'B'

10-10-25W
NE SW SW

Contr. EMPIRE DRLG

GRAHAM County

E 2525RB Comm. 1-25-58 Comp. 2-28-58

IP 219 BOPD

PHY POT

Tops	Depth	Datum
ANH	2150	375
HEEB	3749	-1224
TOR	3774	-1249
LANS	3792	-1267
TD	4015	-1490

Casing

8" 186
5" 4014

CORRECTED CARD

4-11-58

CORRECTED ELEV,
TOPS & DATUM

DST 3758-75/1 HR, G/1½ HR, 1070' OIL,
BHP 1220

DST 3978-4015/1 HR, 690' G, 120' OCM,
60' V H OCM, BHP 340

PERF 24/3989-95: ACID 800: SWB 3/4 BOPH:
ACID 2000: SWB 10 BOPH/9 HR

ELRICK NE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS