

4-032229

S-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,689 -00-00

S2 SE SE /4 SEC. 20, 01, 33 W
330 feet from S section line
660 feet from E section line

Operator license# 5552

Lease: VAP Well # 2

Operator: Gore Oil Company

County: Rawlins 137.70

Address: 202 S. St. Francis
P.O. Box 2757
Wichita, Kansas 67201-2757

Well total depth 4237 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well , Gas well , Input well , SWD , D. & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 21 Month: May Year: 1997

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

6-3-97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:00 P.M., Day: 21 Month: May, Year: 1997

Actual plugging report: 8 5/8" set at 247' w/185 sxs.cwc. 5 1/2" set at 4234' w/250 sxs.
PBTD 4208'. Prod. Perf. 4007' - 4145'. Sanded back to 3900' w/5 sxs on sand with bailer.
Recovered 1618' of casing. Mixed and pumped down 5 1/2" 100 sxs cement blend with 500# hulls
mixed in. Pulled to 300' - circulated with 90 sxs cement blend. Pulled casing. Hole full.
Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through RUBING _____, CASING _____. Elevation: _____ GL

I did / did not observe the plugging.

DATE JUN 05 1997

INV. NO. 48230

Carl Goodrow
(agent)

S-21