

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20718-00-00
Spot: CSWSWNE Sec/Twnshp/Rge: 17-1S-33W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: KOPRIVA B Well Number: 1
County: RAWLINS Total Vertical Depth: 4210 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 734-B NORTH FOUR WHEEL DR.
KINGMAN, KS 67068

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 307
Production: Size 4.5 feet: 4206
Liner: Size feet:

\$ 136.83

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/18/2001 9:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 9 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/18/2001 10:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 307' w/175 sxs cwc. 4 1/2" set at 4206' w/125 sxs.
Prod. Perfs 4120' - 4125'. Exempt area.
Fluid level 4000'.
Three shots recovered 1200' of 4 1/2".
Filled hole with 9 yards Redi-Mix (11 yards by yield).

INVOICED
DATE 6-6-01
INV. NO. 2001061894

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 6 2001
6-6-2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

MAY 30 2001

ALLIED OIL COMPANY
TANEYVILLE, MO 65759

17-01 -33W
SW SW NE

#1 KOPRIVA "B"

site: 10-1/2 N OF ATWOOD, KS
contr: EMPHASIS OIL OPERATIONS

city: RAWLINS API 15-153-20718
field: WC (1/2 S OF RHP SE)

geol: MIKE BAIR

fr date 06/15/88 spd date 07/06/88 drig comp 07/17/88 card issued 10/26/88 last revised 10/26/88

ELV: 2980 KB SMP
tops.....depth/datum
ANH.....2836 +144
B/ANH.....2870 +110
TOP.....3724 -744
DR CR.....3785 -805
OREAD.....3848 -868
HEEB.....3875 -895
LANS.....3920 -940
BKC.....4171 -1191
PBTD.....4177 -1197
RTD.....4210 -1230

IP status:

OIL, P 30 BOPD, NW, LKC 4120-4125,
CSG: 8-5/8" 307 / 175 SX, 4-1/2" 4206 / 125 SX
NO CORES
DST (1) 3940-3990 (LKC), / 30-30-30-30, REC 10' M
ISIP 744# FSIP 694# IFP 25# -25# FFP 27# -29#
DST (2) 3982-4038 (LKC), / 30-30-30-30, REC 31' M
ISIP 38# FSIP 36# IFP 27# -27# FFP 29# -31#
DST (3) 4030-4088 (LKC), / 45-45-45-45, REC 20' SLI
OCM ISIP 1310# FSIP 1305# IFP 29# -28# FFP 47#
-47#
DST (4) 4086-4135 (LKC), / 30-30-90-60, REC 40' MCO
(55% OIL, 45% M), GSY OIL ON TOP OF TOOL ISIP
254# FSIP 881# IFP 25# -25# FFP 27# -29#
MICT - CO, PF (LANS E) 4119.5-4124.5, W / 4 SPF, AC
250 GAL (15% MCA), SO, RE-AC 750 GAL (15% MCA),
SO, RE-AC 2000 GAL (15% CRA), SO, SET 2-3/8" TBG
AT 4169, NO PKR, POP, P 30 BOPD, NW, 8/15/88

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS