

To: 6 100385
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29
API NUMBER 15- 153-20,734-00-00

NW NW SW, SEC. 9, T. 1 S, R. 33 W/E

2310 feet from S section line

4950 feet from E section line

Lease Name Vap Well # 9-40

County Rawlins 136.99

Well Total Depth 4215 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 317

TECHNICIAN'S PLUGGING REPORT

Operator License # 9325

Operator: Allied Oil Company

Name & Address Route 2 Box 45 A

Taneyville, Mo. 65759

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling License Number 8682

Address _____

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19

Plugging proposal received from Dave Pasgal

(company name) Golden Eagle Drilling Inc. (phone) _____

were: Spot through drill pipe w/heavy mud betwen all plugs.

1st plug at 2840' w/25 sks

2nd plug at 2080' w/100 sks

3rd plug at 360' w/40 sks

4th plug at 40' w/wiper plug and 10sks

~~rathole 15 sks/ mousehole 10 sks~~ Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30PM Day: 29 Month: April Year: 19 89

ACTUAL PLUGGING REPORT _____ Hole reported plugged as above.

Order 200 sks 60/40 poz w/6% gel and 2 sks celloflake/flowcele.

Remarks: did not penetrate Asbuckle, cemented by Halliburton

Elevation: 2984'. Anhydrite depth 2834' - 71
(If additional description is necessary, use BACK of this form.)

INVOICED (back of form) observe this plugging.

DATE 5-15-89

INV. NO. 24846

Phil S

Signed David K. Wann (TECHNICIAN)

David K. Wann

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1989
CONSERVATION DIVISION
Wichita, Kansas
5-15-89