

6 030845

JAN 7 1987 15-153-20631-00-01  
API NUMBER 15-153-20631A

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SESESE, SEC. 9, T. 1, S. R. 33 (W/E)

330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8682

Lease Name SRAMEK Well # 9-64

Operator: GOLDEN EAGLE INC.

County RAWLINS 136.34

Name & Address Box 983

Well Total Depth 4195 feet

MCCOOK, NEBRASKA

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 3/8 feet 300'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated OWWO

Plugging Contractor B.J. TITAN License Number \_\_\_\_\_

Address OAKLEY, KANSAS

Company to plug at: Hour: AM Day: 7 Month: 1 Year: 19 87

Plugging proposal received from DARWIN PIERSON

(company name) GOLDEN EAGLE (phone) \_\_\_\_\_

were: ORDER SANDS COM. CNT PULL PIPE ORDER 200SX. THIRTY MIX

5SX. HULLS 65/35 PG 10% GEL 2% DICEI BJTITAN CNT CO.

8 3/8 SET @ 300' CWC. 4 1/2" NA. WEBB WATER TRUCK INTO SWAB TANK

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 AM Day: 7 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT DUMP SAND ON OPEN HOLE TO 4100' SPOT 4SX. COMMENT ON SAND W/BAUER. 5 SHOTS @ 3700', 3500', 2400', 1600' & 1550' RECOVERED 1550' OF 4 1/2" CSG. - MIXED & PUMPED DOWN 8 3/8" 10 bbl CNT. SHURRY (20 SX.) FOLLOWED W/ 110 bbl CNT SHURRY W/ 5SX. HULLS MIXED IN (180 SX) LOADED HOLE & SQUEEZED TO 500# CLOSED IN @ 400# PLUG COMPLETE

Remarks: DAKOTA PLUGGED WITH CNT THROUGH & ACROSS FROM SURFACE (If additional description is necessary, use BACK of this form.)

INVOICED 3700' CEMENT MIX, NO GEL, SPACERS TO SUR. (If additional description is necessary, use BACK of this form.)

DATE 1-20-87

Signed Carl Goodnow (TECHNICIAN) JAN 20 1987

INV. NO. 15958 FEB 10 1987

CONSERVATION DIVISION Wichita, Kansas 1-20-87 FORM CP-2/3 Rev. 01-84