


15-153-20170-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Rawlins County, Sec. 9 Twp. 1 Rge. 33W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE NW
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter
Lease Name Bucy Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 16, 1973 19
Application for plugging filed October 15, 1973 19
Application for plugging approved October 15, 1973 19
Plugging commenced October 16, 1973 19
Plugging completed October 16, 1973 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Depth to top Bottom Total Depth of Well 4150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	246.61	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe at 2025' w/110 cubic feet cement.
Plugged through drill pipe at 275' w/30 cubic feet cement.
Plugged through drill pipe at 40' w/10 cubic feet cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1973
CONSERVATION DIVISION
Wichita, Kansas

10-19-73

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 17th day of October, 1973
August 5, 1975
Virginia S. Fabian, Notary Public.

15-153-20170-00-00

WELL LOG

CHIEF DRILLING CO., INC. &
BILL J. PORTER
Suite 905 Century Plaza
Wichita, Kansas 67202

BUCY #1
SE NW Sec. 9-1-33W
Rawlins County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: Set 246.61' of 8 5/8" w/160
sacks common quick set cement

COMMENCED: 10/6/73
COMPLETED: 10/16/73

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	70	2957 Gr.
Surface Hole	70	255	2959 D.F.
Shale	255	1762	2962 K.B.
Shale & Sand	1762	2588	
Shale & Shells	2588	2804	
Anhydrite	2804	2843	
Shale & Lime	2843	2960	
Lime & Shale	2960	3815	
Lime	3815	4150	
Total Depth	4150		

<u>FORMATION TOPS</u>	
Anhydrite	2804 + 156
Base Anhy.	2843 + 117
Oread	3815 - 853
Lansing	3891 - 929
R.T.D.	4150 - 1188

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NW of Section 9-1-33W, Rawlins County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.


Jim Robinson, Office Manager

Subscribed and sworn to before me this 18th day of October, 1973

Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:

August 1975



RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1973
CONSERVATION DIVISION
Wichita, Kansas