

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,631-00-00

LEASE NAME Sramek

WELL NUMBER 1

330 Ft. from S Section Line

395 Ft. from E Section Line

SEC. 9 TWP. 1 RGE. 33 (E) or (W)

COUNTY Rawlins

Date Well Completed 09-29-85

Plugging Commenced 09-29-85

Plugging Completed 09-29-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RaCo Oil

ADDRESS 408 State Street, Atwood, Kansas 67730

PHONE# (913)-626-9695 OPERATORS LICENSE NO. 4578

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 8 #6

Is ACO-1 filed? Yes If not, is well log attached? Yes #136.50

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	319	8 5/8	319	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4200 to 3570	80 sacks cement @ 240
25 sacks cement @ 3570	10 sacks cement @ 40
30 sacks cement @ 2820	10 sacks cement in rat hole & mouse hole
100 sacks cement @ 2030	

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Golden Eagle Drilling, Inc License No. 8682

Address P. O. Box 983, McCook, Nebraska 69001


STATE OF KANSAS COUNTY OF RAWLINS, ss.

K. L. Reeves

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) KL Reeves

(Address) 408 State Street, Atwood, Ks



SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 85

RECEIVED Notary Public

DATE 10-29-85 My Commission Expires: June 18, 1986

INV. NO. 10818

OCT 17 1985
10-17-85
CONSERVATION DIVISION

15-153-20631-00-00

DRILLERS LOG

OPERATOR: RaCo Oil
408 State Street
Atwood, Kansas 67730

CONTRACTOR: Golden Eagle Drilling, Inc
P. O. Box 983
McCook, Nebraska 69001

LEASE: Sramek WELL: No. 1 LOCATION: SE SE SE
Sec 9-1s-33w
Rawlins County, Kansas

RTD: 4200 LTD: 4196

ELEVATION: 2949 GL 2952 DF 2954 KB

COMMENCED: 09-19-85 COMPLETED: 09-29-85

CASING: 8 5/8" @ 319/210 sacks cement STATUS: D & A

FORMATIONS & DEPTHS

Soil & Clay	0-200
Shale & Redbed	200-1300
Shale & Sand	1300-2800
Anhydrite	2800-2840
Shale & Lime	2840-3650
Lime with shale streaks	3650-4200
RTD	4200

STATE OF KANSAS)
) ss
COUNTY OF RAWLINS)

Richard G. Smith, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Richard G. Smith
Richard G. Smith

Subscribed and sworn to before me this 2nd day of October, 1985.

My Commission Expires: June 18, 1986



[Signature]
Notary Public

WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1985

CONSERVATION DIVISION
Wichita, Kansas

10-17-85