

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20170-06-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1973

CONSERVATION DIVISION
Wichita, Kansas

10-23-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Bucy Well No. 1

Location SE-NW Sec. 9 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 1:30 PM Day 16 Month 10 Year 1973

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1800'.

Circulated hole from bottom with heavy mud. Pulled DP to 2025' and displaced 110 Cu.

Ft. cement thru DP from 2025' to 1700'. Pulled DP to 275' and displaced 30 Cu. Ft.

cement thru DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and

10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 10/23/73

Signed: A. L. Dechels
Well Plugging Supervisor

INV. NO. 8043-W