

8-14

4-032254

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,154-00-00

NW SW \_\_\_\_\_ /4 SEC. 21, 01, 33 W  
1980 feet from S section line  
4620 feet from E section line

Operator license# 3602  
Operator: Philpott Oil & Gas  
Address: P.O. Box 450  
Atwood, Kansas 67730

Lease: Chief Vap "A" Well # 1  
County: Rawlins 135.53  
Well total depth 4170 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 233 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company Northwest Well Serv. License# 31664  
Address: Russell Kansas 67665

Company to plug at: Hour: A.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Roger Philpott

Company: Philpott Oil & Gas Phone: \_\_\_\_\_ - 9-15-97

Were: Order 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:15 A.M., Day: 14 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 233' w/160 sxs cwc. 4 1/2" set at 4169' with 175 sxs. Prod. Perf. At 4084' - 4089'. Recovered 1200' of 4 1/2" w/ shots at 3000' and 2200'. CIBP at 4030'. Hole open to anhy. Mixed and pumped down 8 5/8" w/150 sxs cement blend with 300# hulls mixed into Max. P.S.I. 200#. Hole full. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

*P.*

Form CP-2/3

**INVOICED**

DATE 9-16-97  
INV. NO. 49022  
8-14