

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20169-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1973
10-9-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Inc., & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Vap Well No. A-2

Location SW-SW Sec. 21 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4175'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Inc.,

Address Above License No.

Operation Completed: Hour 1:30 PM Day 4 Month 10 Year 1973

The above well was plugged as follows:

262'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 110 Cu. Ft. cement
thru DP from 2025' to 1700'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar..

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/9/73
INV. NO. 7999-W

Signed: H. S. Nichols
Well Plugging Supervisor