

State of Kansas



15-153-20193-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 P. O. Box 17027 3830 S. Meridian  
 WICHITA, KANSAS 67217

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION  
 Wichita, Kansas

12-2-74

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corp., & Sohio Petr., Co.,

Complete Address: Suite 600, 200 West Douglas, Wichita, Kansas.

Lease Name: Munstermann Well No. B-1

Location: SW-SE Sec. 24 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4245' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sixbury was instructed to plug the well as follows:

321'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*H. L. Nichols*  
 Conservation Division Agent