

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20712-00-01
Spot: CSEENENW Sec/Twnshp/Rge: 24-1S-33W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: TIMM A OWWO Well Number: 4
County: RAWLINS Total Vertical Depth: 4621 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 304 185 SX CMT
Production: Size 4.5 feet: 4394 575 SX CMT
Liner: Size feet: 150.18

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/25/2001 12:00 PM
Plug Co. License No.: 30931 Plug Co. Name: DAYSTAR PETROLEUM, INC.
Proposal Rcvd. from: CHARLES SCHMIDT Company: DAYSTAR PETROLEUM, INC. Phone: (316) 755-3523

Proposed Plugging Method: Order 250 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/25/2001 3:40 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 304' w/185 sxs cwc. 4 1/2" set at 4394' w/575 sxs cwc.
Prod. Perfs 4009' - 4148'.
Squeezed 4 1/2" casing with 280 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 100#. Held.
Tested 8 5/8" to Max. P.S.I. 500#. Cement at surface.
Plug complete.

RECEIVED
AUG - 8 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED
DATE 8-13-01
2002060214

District: 04

Signed Carl Goodrow
(TECHNICIAN)

AUG 02 2001

replacement card

SOURCE PETROLEUM / A DIV OF PRESLEY PETROLEUM CO.
WICHITA, KS 67202

24-01 -33W
SE NE NW

#4 TIMM "A" OWWO

site: 9-3/4 N & 3-1/2 E OF ATWOOD, KS
contr: UNKNOWN

cty: RAWLINS
field: WILHELM

API 15-153-20712

geol:
fr date 06/21/89 spd date 05/23/89 drig comp 05/24/89 card issued 06/21/89 last revised 09/20/89

ELV: 2980 KB LOG
tops.....depth/datum
HEEB.....3919 -939
LANS.....3957 -977
BKC.....4248 -1268
MISS.....4576 -1596
PBD.....4180 -1200
RTD OLD.....4620 -1640

IP status:
OIL, P 10 BO & 5 BWPD, LKC 4147-4151,
INFO RELEASED: 9/20/89 - WAS OIL WELL - TIGHT HOLE
OLD INFO: OPERATOR WAS SOURCE PETROLEUM / A
DIV OF PRESLEY PETROLEUM CO. , 4 TIMM "A", SPD
04/27/88 , 05/01/88 SET 8-5/8" 304 / 185 SX, 4-1/2"
4394 / 575 SX, OIL, P 12 BO & 15 BWPD, LKC 4009-4212
OA, (CARD ISSUED 08/03/88)
CONTR: MURFIN DRILLING COMPANY
GEOL: RANDY LILAK
NO CORES OR DSTS
MICT - CO, PF (LKC) 1/4185, 1/4212, AC 750 GAL (15%
MCA), SO, PF (LKC) 3/4145-4148, 2/4121-4123, 6/4102-
4108, AC 9000 GAL (15% SGA), SO, PF (LKC) 3/4045-
4048, 2/4009-4011, AC 5750 GAL (15% SGA),

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)