

RECEIVED
MAR 22 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 159-21607-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Bear Petroleum, Inc. KCC License #: 4419
(Owner / Company Name) (Operator's)

Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: (316) 524 - 1225

Lease: Wolf Well #: C1 Sec. 6 Twp. 21 S. R. 6 East West

- NW - NW - NE Spot Location / QQQQ County: Rice

4950 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 203 Cemented with: 140 Sacks

Production Casing Size: 5 1/2 Set at: 3526 Cemented with: ? Sacks

List (ALL) Perforations and Bridgeplug Sets: 3463-67', 3476-88'

Elevation: _____ (G.L. / K.B.) T.D.: 3527 P.B.T.D.: 3495 Anhydrite Depth: ?
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand back to 3413', dump bail 5 sax cement, shoot pipe off, pull to 1050', 35 sax, 650', 35 sax, 258', circulate to surface, 60/40 poz 4% gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bear Petroleum, Inc. Phone: (316) 524 - 1225

Address: P.O. Box 438 City / State: Haysville, KS 67060

Plugging Contractor: Mikes Testing & Salvage KCC License #: 31529
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524-0467 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): unknown


Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-19-04 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
 MAR 22 2004
 KCC WICHITA

SHER-LON CORPORATION
 320 S. BROADWAY
 STERLING, KS 67579
 CONTR DUKE DRILLING CO., INC. #1 "C" WOLF 6-21-6W
 NW NW NE
 CTY RICE
 GEOL _____ FIELD WELCH-BORNHOLDT
 ELV 1686 KB SPD 7/18/83 CARD ISSUED 10/20/83 IP P 17 BOPD
 MISS 3463-3488 OA
 API 15-159-21,607



LOG	Tops	Depth/Datum	
HEEB	2731-1045	8 5/8 " 203/140SX; 5 1/2 " 3526 NO DST'S MICT - CO, PF (MISS) 3463-67, 3476-88, FRAC 200,000GW & 20,000# SD, SWB LD, GSO, T&R, POP, P 17 BOPD, 9/1/83
BR LM	2907-1221	
LANS	2932-1246	
SWOPE	3199-1513	
PENN CONG	3428-1742	
MISS	3460-1774	
RTD	3527-1841	

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

March 24, 2004

Re: WOLF #C-1
API 15-159-21607-00-00
NWNWNE 6-21S-6W, 4950 FSL 2310 FEL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely



David P. Williams
Production Supervisor