

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-163-01774-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 04-19-1950

Well Operator: H & B Petroleum Corporation KCC License #: 32158
(Owner / Company Name) (Operator's)

Address: P.O. Box 277 City: Ellinwood

State: Kansas Zip Code: 67526 Contact Phone: (620) 564 - 3002

Lease: Darrel Well #: 2 Sec. 34 Twp. 9 S. R. 20 East West

C - NE - NE - NW Spot Location / QQQQ County: Rooks

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310-990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 1759 Cemented with: 750 Sacks

Production Casing Size: 5 1/2 Set at: 3823 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: CIBP 3750 Open Hole 3823 to 3827

Elevation: 2264 (G.L. / K.B.) T.D.: 3827 PBTD: 3750 Anhydrite Depth: 1752
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

310 sxs 60/40 pos w/ 10% gel and 500# hulls total. Tubing to 3700'. Spot 100 sxs w/ 200# hulls, 2255'; 100 sxs w/ 200# hulls, 800'; 60 sxs w/ 100# hulls. Squeeze from surface. Check braden head.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

RECEIVED
APR 26 2004
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Al Hammersmith

H & B Petroleum Corporation Phone: (620) 564 - 3002

Address: P.O. Box 277 City / State: Ellinwood, Kansas 67526

Plugging Contractor: Allied Cementing KCC License #: Non required

Address: 24 South Lincoln St., Russell, Kansas 67665 Phone: (785) 483 - 2627
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 04-22-2004 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 04-21-2004 Authorized Operator / Agent: Al Hammersmith
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202