

11-7

153-20-763 -00-00

6 062266

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE, SEC. 25, T 1 S, R 33 W/E

2145 feet from S section line

1815 feet from E section line

TECHNICIAN'S PLUGGING REPORT
3602

Operator License #

Lease Name Simminger Well # 2-1025

Operator: Philpott Oil and Gas Co. Inc.

County Rawlins 138.93

Name & Address: Box 450

Well Total Depth 4275 feet

Atwood, Ks. 67730

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 275 w/185 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Golden Eagle Drilling Inc. License Number 8682

Address Atwood, Ks. 67730

Company to plug at: Hour: 11:10 AM Day: 6 Month: Nov Year: 19 90

Plugging proposal received from Dave Pascal

(company name) Golden Eagle Drilling Inc. (phone)

were: Order 200 sks 60/40 poz 6% gel 1 sk f.c. and 8 5/8 plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 2:00AM Day: 7 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 4275 w/25 sks

2nd plug at 2025 w/100 sks 1 sk f.c.

3rd plug at 325 w/40 sks.

4th plug at 40 w/10 sks

15 sks in rathole 10 sks in mousehole.

RECEIVED
STATE CORPORATION COMMISSION
11-15-90
NOV 15 1990

Remarks: Halliburton

(if additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE NOV 27 1990

Signed *Gilbert G. Scheck*
(TECHNICIAN)
Gilbert G. Scheck

REV. NO. 30042