

6050153

API NUMBER 15-153-20,583-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. SE. NE, SEC. 25, T. 1 S, R. 33 W/EX

3300 feet from S section line

600 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Simminiger Well # 1

Operator: Abercrombie Drilling

County Rawlins 141.05

Name & Address 801 Union Center

Well Total Depth 4340 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 303 w/200 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie License Number 5422

Address Same as above

Company to plug at: Hour: PM Day: 27 Month: November Year: 19 84

Plugging proposal received from Walley Towns

(company name) Abercrombie (phone) \_\_\_\_\_

were: Order 200 lbs. 50/50 pozmix 6% gel 3% cal-cl. 1 sk flo-cel, 1 sk hulls and 8 5/8"  
plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with  
good circulation and no fluid loss.

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 7:30 PM Day: 27 Month: November Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 2880 w/20 sks

2nd plug @ 2160 w/110 sks 1 sk flo-cel

3rd plug @ 340 w/40 sks

4th plug @ 40 w/8 5/8" plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole and 10 sks in Mouse Hole

Remarks: Cemented by Sun

(If additional description is necessary, use BACK of this form.)

(did, did not) observe this plugging.

DATE 12 12 84

INV. NO. 5936

Signed Gilbert P. Liker (TECHNICIAN) 11-30-84

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 03 1984  
CONSERVATION DIVISION  
Wichita, Kansas