

To: **6 050036**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-8

API NUMBER 15-153-20733-00-00
NE NW , SEC. 31, T. 1 S, R 33 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3750

Operator: Turnpike Oil Co.
Name & Address 5810 W. 38th Ave #12
Denver, Co. 80212

Lease Name Walters Well # 3-31
County Rawlins 138.13
Well Total Depth 4250 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well Input Well SWD Well U&A x
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033
Address Wichita, Ks.

Company to plug at: Hour: PM Day: 8 Month: April Year: 19 89

Plugging proposal received from Keith Vantale
(company name) Murfin Drilling Co. (phone)

were: Order 190 sks 60/40 Poz 6% Gel 3% CaI Cl 1 sk F.C. and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis. mud between all plugs with
good circulation and no fluid loss.

Plugging Proposal Received by Bruce D. Basye
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 11:30AM Day: 8 Month: April Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2890' w/25 sks Anhy
2nd plug at 2115' w/100 sks 1 sk F.C. Dakota
3rd plug at 365' w/40 sks
4th plug at 40' w/10 sks
15 sks in rathole

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1989
4-21-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
(If additional description is necessary, use BACK of this form.)

INVOICED
If back observe this plugging.

DATE 4-27-89
INV. NO. 24575

Red S

Signed Bruce D. Basye
(TECHNICIAN)
Bruce D. Basye