

To: **6 031460**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-10
API NUMBER 15- 153-20,732-00-00 **3258**

NW SE, SEC. 30, T 1 S, R 33 W&E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 03750
Operator: Turnpike Oil Co.
Name & Address: 5810 W 38th Ave. #12
Denver, Colorado 80212

Lease Name Vap Well # 10-30
County Rawlins **139.26**
Well Total Depth 4285 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated
Halliburton Services

Plugging Contractor License Number
Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 10 Month: Dec Year: 19 90

Plugging proposal received from Walt Smith
(company name) Turnpike (phone)

were: 8 5/8 set at 325 w/200 sks ewc. 5 1/2 set at 4280 w/350 sks.
TOC 1530. PBDT 4248. Perf 4088 - 4186. Order 425 sks 65/35 poz 8% gel
500 lbs. hulls. Halliburton Cement Co. Webb WaterTrucks.
Pulled rods and pump w/3 3/8 tubing out of hole. Hole open across perfs.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:35AM Day: 10 Month: Dec Year: 19 90

ACTUAL PLUGGING REPORT Pump down 5 1/2 300 sks cement blend w/450 lbs. hulls
mixed in to max psi 500 lbs. Close in psi 300 lbs. Sq 8 5/8 w/125 sks
cement blend w/50 lbs. hulls. mixed into max psi 200 lbs. Close in psi 200 lbs.
Plug complete.

Remarks: **INVOICED** (did/did not observe this plugging.)
Additional description is necessary. Use BACK of this form.)
Wichita, Kansas

DATE **JAN 18 1991**
INV. NO. **20539**

Signed **Carl Goodrow**
(TECHNICIAN)
Carl Goodrow