

4-032230

5-22

API Number: 15-153-20,980 - 00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE NE /4 SEC. 29, 01, 33 W
4620 feet from S section line
660 feet from E section line

Operator license# 5552

Lease: Worley "A" Well # 1

Operator: Gore Oil Company

County: Rawlins 152.13

Address: 202 S. St. Francis
P.O. Box 2757
Wichita, Kansas 67201-2757

Well total depth 4681 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 22 Month: May Year: 1997

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

Handwritten notes and stamps on the right side of the form.

Plugging Proposal Received by: Carl Goodrow 6-3-97

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:30 P.M., Day: 22 Month: May Year: 1997

Actual plugging report: 8 5/8" set at 255' w/225 sxs.cwc. 5 1/2" set at 4680' w/240 sxs.
PBT 4085'. Prod. Perf. 4004' - 4049'. Sanded back to 3900' w/5 sxs common cement on sand
with bailer. Recovered 1603' of casing. Mixed and pumped down 5 1/2" 90 sxs cement blend
with 500# hulls mixed in. Pulled 5 1/2" to 300' - circulated cement to surface with 160 sxs
cement blend. Pulled casing. Hole full. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Signature of Carl Goodrow (agent)

DATE JUN 05 1997

INV. NO. 48232

5-22

INVOICED