

5-20

4-032231

API Number: 15-153-20,691-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE NW NE /4 SEC. 29, 01, 33 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 5552

Lease: Worley "B" Well # 1

Operator: Gore Oil Company

County: Rawlins 138.13

Address: 202 S. St. Francis  
P.O. Box 2757  
Wichita, Kansas 67201-2757

Well total depth 4250 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 272 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 20 Month: May Year: 1997

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ ], Part [ X ], None [ ] 6-3-97

Completed: Hour: 7:00 P.M., Day: 20 Month: May Year: 1997

Actual plugging report: 8 5/8" set at 272' w/185 sxs.cwc. 5 1/2" set at 4242' w/250 sxs.  
Prod. Perf. 4154' - 4158'. Recovered 1756' of casing. Mixed and pumped down 5 1/2" casing  
100 sxs cement blend with 500# hulls mixed in. Pulled to 300' and circulated with 85 sxs  
cement blend. Pulled casing. Hole full. Plug compelte.

Remarks:  
Condition of casing(in hole): GOOD BAD Any plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did X did not [ ] observe the plugging.

Carl Goodrow (agent)

INVOICED  
DATE JUN 05 1997  
INV. NO. 48231  
5-20