

To: 6 031251
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 165'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-6
API NUMBER 15- 153-20,735 -00-00
w of c NE SEC. 27, T 1 S, R 33 W/E
NW

TECHNICIAN'S PLUGGING REPORT

Operator License # 9800

Operator: Double R. Oil Co.
Name & Address: Box 450
Atwood, Ks

Lease Name Huss Well # D-1

County Rawlins 138.13

Well Total Depth 4250 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling Co. License Number 8682

Address _____

Company to plug at: Hour: _____ AM Day: 6 Month: May Year: 19 89

Plugging proposal received from Dave Paschall

(company name) Golden Eagle (phone) _____

were: 8 5/8" set at 286' cwc w/185 sks circ hole w/no less than 36 vis mud/w no loss

or gain of fluids. Spot cement plugs w/drill pipe. Balance plugs w/mud. Order 200 sks
60/40 poz 6% Gel 3% cc 8 5/8" w.p. B.J. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:00 A.M. Day: 6 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2850' w/25 sks

2125' w/100 sks, ^{sk}Hulls

340' w/40 sks

40' w/10 sks

15 sks rathole

10 sks in mousehole

Remarks: (If additional description is necessary, use BACK of this form.)

I () did not observe this plugging.

DATE 6-7-89

INV. NO. 25003

JUL 11 1989

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow