

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,413-0000

LEASE NAME Wolters

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 34 TWP. 1S RGE. 33 (W) or (W)

COUNTY Rawlins

Date Well Completed 4/1/81

Plugging Commenced 11/6/84

Plugging Completed 11/6/84

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE#(316 267-3241) OPERATORS LICENSE NO. 6033

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays - Carl Goodrow

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Top/LKC Depth to Top 3868' Bottom 4196' T.D. 4280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 50 sx. 50-50 Pozmix & 3 sx. Halls placed at 4233' to 3480'. Pumped 25 sx. Gel placed at 3480' to 1881'. Pumped 180 sx. 50-50 Pozmix placed at 1881' to surface. Pressured to 600#. Cut casing off 5' below ground level.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address Wichita, KS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

L.O. Butner, Western Div., Prod. Mgr. (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: L.O. Butner

(Address) 250 N. Water, Suite 300; Wichita, KS

SUBSCRIBED AND SWORN TO before me this 11 day of December, 1984

My Commission Expires: 2/6/85 Kerran Redington Notary Public



WELL LOG

15-153-20413-000

COMPANY Murfin Drilling Company

SEC. 34 T. 1S R. 33W

FARM WOLTERS

NO. 2-34 Inj.

LOC. SE NE NW


RIG. NO. 7

TOTAL DEPTH 4280'

COMM. 2-7-81

COMP. 2-15-81

COUNTY Rawlins KANSAS



CONTRACTOR Murfin Drilling Company

CASINO

20 10

15 8 - 5/8" set at 298' w/275 sx. 60-40 Sunset.

12 6

13 5

4 1/2" set at 4279' w/50 sx. Class A + 125 sx.

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 3054' KB
3049' GL

PRODUCTION
50-50 Pozmix. 2nd Stage:
500 sx. Howcolite + 100 sx.
50-50 Pozmix.

Sand and post rock	255'
Shale	1365'
Shale and Sand	2685'
Red Bed	2873'
Anhydrite	2910'
Shale and Lime	3795'
Lime and Shale - RTD	4280'

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1984

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, Wm. S. Shropshire, Asst. Gen. Mgr. of the Murfin Drilling Company Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Wolters #2-34 Inj. well.

MURFIN DRILLING COMPANY

By: Wm. S. Shropshire, Asst. Gen. Mgr.

Subscribed and sworn to before me this 22 day of July 19 81



Kerran Redington
NOTARY PUBLIC
Kerran Redington