

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-153-20,583-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Abercrombie Drilling, Inc. OPERATORS LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) SIMMINGER WELL NO. 1 WELL LOCATION C SE NE COUNTY Rawlins

SEC. 25 TWP. 1S RGE. 33W (E) or (W)  TOTAL DEPTH 4340' PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A    SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 303' CEMENTED WITH 200 SACKS

CASING SIZE --- SET AT --- CEMENTED WITH --- SACKS

PERFORATED AT -----

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 2880' with 20 sx., 2nd plug @

2160' with 110 sx. 1 sx. Flocel. 3rd plug @ 340' with 40 sx. 4th plug @ 40' Sol. Bridge with

10 sx. 10 sx. in Rathole. 10 sx. in Mousehole. 50-50 pozmix, 6% gel, 3% c.c.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NO

(If not, explain)

Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:15 p.m., 11/27/84

RECEIVED  
STATE CORPORATION COMMISSION  
6-28-84  
DEC 28 1984  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wally Towns (Toolpusher) PHONE # (913) 462-2123

ADDRESS R.R. #2 Box 1159, Colby, KS 67701

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack L. Partridge  
(Operator or Agent)

DATE: December 3, 1984  
Jack L. Partridge, Vice President