

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-153-20712 -00-01

LEASE NAME Timm A

WELL NUMBER 4

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC 24 TWP 1 RGE 33 W

COUNTY Rawlins

Date Well Completed 5/26/89

Plugging Commenced 7/25/01

Plugging Completed 7/25/01

RECEIVED

AUG 13 2001

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Daystar Petroleum, Inc.

ADDRESS 1321 W. 93rd N., Valley Center, KS 67174

PHONE # 316-755-3523

Character of Well oil

(Oil, Gas, D & A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/25/01 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing Depth to Top 3957 Bottom 4576 T.D. 4620

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	Oil	0	304	8 5/8	304	0
		0	4394	4 1/2	4394	0

Describe in detail the manner in which the well was plugged, indicating where the mud was fluid placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Pressured surface - production csg annulus to 500 psi - held solid  
pumped 250 sx 60-40 poz w/ 500 # hulls from surface to approx 4200'.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 5549

Address P.O. Box 628, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Daystar Petroleum, Inc.


STATE OF KANSAS COUNTY OF Sedgwick, ss.

Charles Schmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Schmidt

(Address) 1321 W. 93rd N., Valley Center, KS 67147

SUBSCRIBED AND SWORN TO before me this 9th day of August 2001



My commission Expires: 9-15-2003

Marsha Breitenstein  
Notary Public

OR

# ALLIED CEMENTING CO., INC.

7161

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>7-25-01</u>	SEC. <u>24</u>	TWP. <u>1 S</u>	RANGE <u>W 33</u>	CALLED OUT	ON LOCATION <u>2:40 PM</u>	JOB START <u>3:00 PM</u>	JOB FINISH <u>3:45 PM</u>
LEASE <u>Tiam</u>	WELL # <u>A-4</u>	LOCATION <u>Ludell 7 1/2 mi SW into</u>		COUNTY <u>Rowles</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)							

CONTRACTOR \_\_\_\_\_  
 TYPE OF JOB Plug old Hole  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 DEPTH \_\_\_\_\_  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 500# MINIMUM 150#  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. 4183-4185  
 DISPLACEMENT \_\_\_\_\_

OWNER same  
 CEMENT AMOUNT ORDERED  
250 sk 60/40 Poz 10% Gel  
10sk Gel + 500# Hulls on side  
 COMMON 150 sks @ 7.85 1177.50  
 POZMIX 100 sks @ 3.55 355.00  
 GEL 21 sks @ 10.00 210.00  
 CHLORIDE \_\_\_\_\_  
 Hulls 9 sks @ 8.00 72.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 HANDLING 287 sk @ 1.10 309.10  
 MILEAGE 48 sk/mile 730.60  
 TOTAL 2854.20

EQUIPMENT  
 PUMP TRUCK CEMENTER Dean  
 # 191 HELPER Andrew  
 BULK TRUCK  
 # 218 DRIVER Fuzzy  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:  
Pressure Back side 500# Hold  
No Cement, Pump down 4 1/2 csg  
250 sk w/ 10% Gel + 500# Hulls.  
Max Pressure 150#

SERVICE  
 DEPTH OF JOB \_\_\_\_\_  
 PUMP TRUCK CHARGE \_\_\_\_\_ 475.00  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 65 miles @ 3.00 195.00  
 PLUG @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

CHARGE TO: Dexter Pet.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

RECEIVED TOTAL 620.00  
 AUG 13 2001  
 FLOATED EQUIPMENT  
 KCC WICHITA @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL \_\_\_\_\_  
 TAX \_\_\_\_\_  
 TOTAL CHARGE 3524.20  
 DISCOUNT 352.42 IF PAID IN 30 DAYS  
3171.78

SIGNATURE AM Walker

PRINTED NAME \_\_\_\_\_