

15-153-20169-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rawlins County. Sec. 21 Twp. 1 Rge. 33W (E) (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines. SW SW  
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter  
Lease Name Vap A Well No. 2  
Office Address 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10/4/73 19  
Application for plugging filed 10/3/73 19  
Application for plugging approved 10/3/73 19  
Plugging commenced 10/4/73 19  
Plugging completed 10/4/73 19  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well 4145' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	256'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Plugged through drill pipe at 2025' w/110 cubic feet cement.  
Plugged through drill pipe at 275' w/30 cubic feet cement.  
Plugged through drill pipe at 40' w/10 cubic feet cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 10 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc. 10-10-73  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Jim Robinson  
905 Century Plaza, Wichita, Kansas (Address)

Subscribed and sworn to before me this 9th day of October, 1973  
My commission expires August 5, 1975  
Virginia S. Fabian, Notary Public.



15-153-20169-00-00

WELL LOG

CHIEF DRILLING CO., INC. &  
BILL J. PORTER  
Suite 905 Century Plaza  
Wichita, Kansas 67202

VAP "A" #2  
SW SW Sec. 21-1-33W  
Rawlins County, Kansas

CONTRACTOR: Company Tools  
CASING RECORD: Set 256' of 8 5/8" w/160  
sacks common quick set cement

COMMENCED: 9/25/73  
COMPLETED: 10/4/73

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1973

CONSERVATION DIVISION  
Wichita, Kansas

10-10-73

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Sand & Gravel	0	265
Shale & Sand	265	400
Shale	400	1850
Shale & Shells w/Sand Strks.	1850	2400
Lime & Shale	2400	3802
Lime	3802	4145
Total Depth	4145	

ELEVATION

2944 Gr.  
2946 D.F.  
2949 K.B.

FORMATION TOPS

Anhydrite	2787 +	162
Base Anhy.	2831 +	118
Oread	3840 -	891
Lansing	3900 -	951
R.T.D.	4145 -	1196

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SW of Section 21-1-33W, Rawlins County, Kansas, to the best of my know ledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson, Office Manager

Subscribed and sworn to before me this 9th day of October, 1973

Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:  
August 1975

