

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-153-05266-00-00

Rawlins County, Sec. 29 Twp. 1-S Rge. 32 XX (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Sam G. Harrison, Trustee
Lease Name Leseberg Well No. 1
Office Address 2418 Bank of the Southwest Bldg., Houston 2, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 9, 1961 19
Application for plugging filed July 9, 1961 19
Application for plugging approved July 9, 1961 19
Plugging commenced July 9, 1961 19
Plugging completed July 9, 1961 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Clay-Sand-Shale	0	470	8 5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 600' with 20 sacks cement.
Plug set at 240' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
07-20-1961
JUL 23 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Theodore Gore (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore

650-4th Nat'l. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 19 61

My commission expires October 21, 1962

Lucille H. Harr
Lucille H. Harr
Notary Public.



LOG

15-153-05266-00-00

COMPANY: Sam G. Harrison, Trustee, Houston, Texas

CONTRACTOR: Empire Drilling Company, Wichita, Kansas

FARM: Leseberg # 1

LOCATION: C NE NW of Section 29-1S-32W, Rawlins County, Kansas

COMMENCED: June 29, 1961

ELEVATION: 2995 KB

COMPLETED: July 9, 1961

POTENTIAL: D & A

0	to	190	Surface Clay
190	to	205	Sand
205	to	470	Shale
470	to	2338	Sand-Shale
2338	to	2485	Shale-Shells
2485	to	2660	Gyp-Shale
2660	to	2779	Shale-Shells
2779	to	2821	Anhydrite
2821	to	2835	Shale
2835	to	2995	Lime-Shale
2995	to	3285	Shale
3285	to	3345	Lime
3345	to	3660	Shale-Lime
3660	to	3708	Lime
3708	to	3770	Lime-Shale
3770	to	3845	Broken Lime
3845	to	3953	Lime-Shale
3953	to	4170	Lime
4170			Rotary Total Depth

SET: 260* 8 5/8" casing with 150 sacks cement.

ELECTRIC LOG TOPS:

Must be obtained from Sam G. Harrison

CERTIFICATION

I, Theodore Gere, do hereby certify that the above and foregoing is a true and correct copy of the log on the Leseberg # 1, C NE NW of Section 29-1S-32W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

Theodore Gere
THEODORE GERE

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 18th day of July, 1961.

Lucille H. Harr
Lucille H. Harr, Notary Public

My commission expires Oct. 21, 1962.

RECEIVED
STATE CORPORATION COMMISSION
07-20-1961
JUL 20 1961

CONSERVATION DIVISION
Wichita, Kansas