

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,195-00-01

LEASE NAME Kompus

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 33 TWP. 1S RGE. 32W ~~KXXXX~~(W)

COUNTY Rawlins

Date Well Completed March, 1975

Plugging Commenced 11:30 A.M.,
3-24-92

Plugging Completed 2:45 P.M.,
3-24-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 22, 1992 (date)

by District #4 - Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No - not available

Producing Formation Lansing/KC Depth to Top 3852' Bottom 3994' T.D. 4080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing/KC	oil & water	3852'	3994'	8-5/8"	295'	-0-
				4-1/2"	4060'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. The casing was perforated 2 shots each @ 3812', 2662', and 1973' prior to cementing. Down 4-1/2" casing @ 700# maximum pressure - mixed 4 sks. hulls w/325 sks. cement & shut in @ 400#. Down 8-5/8" casing @ 600# maximum pressure - mixed 1 sk. hulls w/100 sks. cement & shut in @ 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. 51

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 30th day of March, 19 92

Margaret A. Schulte
Notary Public

My Commission Expires: _____ Margaret A. Schulte



RECEIVED
STATE CORPORATION COMMISSION
APR 01 1992
CONSERVATION DIVISION
Wichita, Kansas