

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

15-153-20376-00-00

COUNTY Rawlins SEC. 33 TWP. 1s RGE. 32w E/W  
 Location as in quarters or footage from lines:  
150' N C NW SW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Murfin Drilling Co.  
 Lease Name Kompus "B" #1 Well No. \_\_\_\_\_  
 Office Address 617 Union Center, Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 11/4/82  
 Plugging completed 11/6/82  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	274'	none
				4 1/2"	4123'	1827'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged bottom with 4 sacks cement, sand to 4800' & 4 sacks cement.

Shot well 3 times, got loose at 1827', pulled 43 joints. Plugged off  
 with 2 sacks hull, 2 gel, 100 cement, 38 gel, plug & 60 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrel Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature)

R. Darrel Kelso  
 Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November 1982



My Commission expires:

RECEIVED  
 STATE CORPORATION COMMISSION  
 Notary Public.  
 NOV 29 1982  
 11-29-1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG

COMPANY Murfin Drilling Company  
FARM KOMPUS "B" NO. 1  
RIG. NO. 7  
TOTAL DEPTH 4150'  
COMM. 4-23-80  
CONTRACTOR Murfin Drilling Company

SEC. 33 T. 1S R. 32W  
LOC. C NW SW

15-153-20376-00-00

WELL FILE

COUNTY Rawlins  
KANSAS


CASINO  
20  
15  
12  
13

10  
8 -5/8" csg. set @ 274' w/250 sx. of  
6 60-40 posmix, w/sunset.

ELEVATION 2941' GL  
2946' KB

5  
4 1/2" csg. set @ 4128' w/200 sx. (50 sx. of Class A, 75 sx. of 50-50 posmix,  
FIGURES INDICATE BOTTOM OF FORMATIONS  
2% gel, 18% salt, 3/4% CFR-2 + 75 sx. of 50-50 posmix, 2% gel, 18%  
salt, 3/4% CFR-2, w/40 gallons of Latex, 2% CC.

PRODUCTION

90' Surface soil & sand  
210' Clay & Sand  
1180' Shale  
2701' Shale & Sand  
2740' ANHYDRITE  
2835' Lime & Shale  
3445' Shale & Lime  
3780' Lime & Shale  
3845' Lime  
4150' Lime & Shale R T D

State of KANSAS  
County of SEDGWICK

I, David L. Murfin, Drlg. Mgr. of the MURFIN DRILLING Company

upon oath state that the above and foregoing is a true and correct copy of the log of the KOMPUS "B" #1 well.

*David L. Murfin*  
David L. Murfin, Drlg. Mgr.

Subscribed and sworn to before me this 16th day of May 1980

My Commission Expires: May 21, 1983

LINDA LYNCH  
STATE NOTARY PUBLIC  
Sedgewick County, Kansas  
My April Exp. 5-21-82

*Linda Lynch*  
Linda Lynch NOTARY PUBLIC