



15-153-20051-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
8-12-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Scarbrough of Thomas Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Scarbrough guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: McCasland Building, Duncan, Oklahoma.

Lease Name: Bolte Well No. 1

Location: CNW-NW Sec. 34 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4660' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Scarbrough was instructed to plug the well as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1130'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 125 Sx.  
cement thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent