

WELL PLUGGING RECORD
K.A.R. 82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-163-22283-00-00
LEASE NAME Look
WELL NUMBER 1
990 ft. from S Section Line
4950 330 ft. from E Section Line
SEC. 17 TWP. 7 RGE. 17 (E) or (W)
COUNTY Rooks
Date Well Completed
Plugging Commenced 3/16/04
Plugging Completed 3/17/04

LEASE OPERATOR Black Diamond Oil, Inc.
ADDEESS Box 641, Hays, KS 67601
PHONE # (785) 625-5891 OPERATORS LICENSE NO. 7076
Character of well ~~oil~~ SWD

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 3/16/04 (date)
by Herb Deines (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached not available to us

Producing Formation Arbuckle Depth to Top 368 Bottom T.D. N/A
Show depth and thickness of all water, oil and gas formations 3325

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surf Prod				8 5/8	1191	none
				5 1/2	3325 3324	2220

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 3264, bail 5 sacks cement. Rip pipe at 2430, 2220', work free. Pull to 1250, pump 75 sacks cement and 3 hulls. Pull to 550, pump 30 sacks cement and 1 hulls. Pull to 200, circulate cement to surface with 45 sacks. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Lehige (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) *Kenneth Lehige*

(Address) P.O. Box 641, Hays, KS 67601



SUBSCRIBED AND SWORN TO before me 14th day of April, 20 04

Verdam Brin
Notary Public

My commission Expires: 7-18-2007

RECEIVED

APR 19 2004

KCC WICHITA

Form CP-4
Revised 05-88

ALLIED CEMENTING CO., INC.

16831

Federal Tax I.D.# ~~XXXXXXXXXX~~

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
2

DATE <u>3-17-04</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START <u>2:00pm</u>	JOB FINISH <u>3:00pm</u>
LEASE <u>LOOK</u>	WELL# <u>1</u>	LOCATION <u>STOCKTON 1E 4S</u>			COUNTY <u>ROCKS</u>	STATE <u>KS</u>	
<u>(O)</u> OLD OR NEW (Circle one)							

CONTRACTOR QUALITY
 TYPE OF JOB PTA
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT
 AMOUNT ORDERED 150 60% 10% GEL
5 HULLS

EQUIPMENT
 PUMP TRUCK CEMENTER MARK
 # 366 HELPER BILL
 BULK TRUCK
 # 282 DRIVER CRATE
 BULK TRUCK
 # _____ DRIVER _____

COMMON	<u>90</u>	@	<u>7.15</u>	<u>643.60</u>
POZMIX	<u>60</u>	@	<u>3.80</u>	<u>228.00</u>
GEL	<u>11</u>	@	<u>10.00</u>	<u>110.00</u>
CHLORIDE		@		
ASC		@		
HULLS	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
HANDLING	<u>166</u>	@	<u>1.15</u>	<u>190.90</u>
MILEAGE	<u>.05/3/4/mi.</u>			<u>489.70</u>
TOTAL				<u>1,752.10</u>

REMARKS:

75 SIL @ 1200 w/3 HULLS
30 SIL @ 550 w/1 HULL
45 SK @ 200 CONC. CEMENT

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>59 mi.</u>	@	<u>3.50</u>	<u>206.50</u>
TOTAL				<u>681.50</u>

CHARGE TO: BLACK DIAMOND
 STREET _____
 CITY _____ STATE _____ ZIP _____

RECEIVED

APR 19 2004

KCC WICHITA

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment
 and furnish cementer and helper to assist owner or
 contractor to do work as is listed. The above work was

PLUG & FLOAT EQUIPMENT

MANIFOLD	@		
	@		
	@		
	@		