

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20051-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
8-12-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address McCasland Building, Duncan, Oklahoma.

Lease Name Bolte Well No. 1

Location CNW-NW Sec. 34 Twp. 1 Rge. (E) (W) 33

County Rawlins Total Depth 4660'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #400, Duncan, Oklahoma. License No.       

Operation Completed: Hour 12:00 PM Day 6 Month 8 Year 1969

The above well was plugged as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1130'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 125 Sx. cement thru  
DP from 1350' to 950'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from  
300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/12/69

INV. NO. 281-W

Signed: M. L. Nichols  
Well Plugging Supervisor