

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20112-00-00  
Spot: SWSW Sec/Twnshp/Rge: 35-20S-7W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WILHAUS Well #: 2  
County: RICE Total Vertical Depth: 3571 feet

Operator License No.: 3911

PROD Size: 5.5 feet: 3370 75 SX CMT

Op Name: RAMA OPERATING CO., INC.

SURF Size: 8 feet: 213 20 SX CMT

Address: 101 S. MAIN  
STAFFORD, KS 67578

06  
#216

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/14/2004 9:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,320' and top with 5 sxs. cement. Shoot casing off. Pull casing to 1,075' and spot 35 sxs. cement. Pull casing to 600' and spot 35 sxs. cement. Pull casing to 265' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/14/2004 3:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,320' and topped with 5 sxs. cement. Shot casing off at 2,320'. Pulled casing to 1,093' and spotted 35 sxs. cement. Pulled casing to 589' and spotted 35 sxs. cement. Pulled casing to 274' and circulated 100 sxs. cement to the surface.

RECEIVED  
KCC DISTRICT #2

MAY 7 2004

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #18294.

Plugged through: CSG

District: 02

Signed

*Michael Wilson*

(TECHNICIAN)

INVOICED

DATE 5-12-04

INV. NO. 2004061559