

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20936-00-00  
Spot: NWSE Sec/Twnshp/Rge: 3-34S-29W  
1980 feet from S Section Line, 1850 feet from E Section Line  
Lease Name: HISSOM Well #: 1-3  
County: MEADE Total Vertical Depth: 5874 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

CIBP Size: feet: 5821 WITH 2 SX CMT  
PROD Size: 4.5 feet: 5831 WITH 195 SX CMT  
SURF Size: 8.625 feet: 1473 WITH 615 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2004 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1480' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2004 1:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:  
PBTD 5821'. PUMP 25 SX CMT & 400# HULLS. 1ST PLUG SPOT 50 SX CMT & 10 SX GEL @ 1495'. 2ND PLUG PULL TO 500' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED  
MAY 12 2004  
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
5831	5874	OH	
5752	5756		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3020' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAY 7 2004  
KCC Dodge City

Signed: \_\_\_\_\_  
(TECHNICIAN)

INVOICED  
DATE 5-12-04  
INV. NO. 2004061560