

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20123-00-00  
Spot: NWSW Sec/Twnshp/Rge: 35-20S-7W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WILHAUS Well #: 4  
County: RICE Total Vertical Depth: 3394 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

PROD Size: 5.5 feet: 3383 75 SX CMT  
SURF Size: 8.625 feet: 200 150 SX CMT *8/110<sup>31</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2004 8:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,330' and top with 5 sxs. cement. Shoot casing off. Pull casing to 1,075' and spot 35 sxs. cement. Pull casing to 600' and spot 35 sxs. cement. Pull casing to 250' and circulate cement to the surface.  
RECEIVED  
KCC DISTRICT #2  
MAY 7 2004

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

WICHITA, KS

Date/Time Plugging Completed: 04/16/2004 1:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,330' and topped with 5 sxs cement. Shot casing off at 2,380'. Pulled casing to 1,065' and spotted 35 sxs. cement. Pulled casing to 564' and spotted 35 sxs. cement. Pulled casing to 251' and circulated 115 sxs. cement to the surface.

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #18269.

Plugged through: CSG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 5-12-04  
INV. NO. 2004061559