

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-30179-00-01  
Spot: S2S2SW Sec/Twnshp/Rge: 35-20S-7W  
660 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: WILHAUS Well #: 1  
County: RICE Total Vertical Depth: 3405 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

PROD Size: 6 feet: 3386 100 SX CMT  
SURF Size: 8.625 feet: 250

110<sup>64</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2004 3:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,335' and top with 6 sxs. cement. Shoot casing off. Pull casing to 1075' and spot 50 sxs. cement. Pull casing to 600' and spot 50 sxs. cement. Pull casing to 300' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/16/2004 5:15 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,330' and topped with 6 sxs. cement. Perforated casing at 1,075', 600', and 300'. Ran 2 7/8" tubing to 1,075' and spotted 50 sxs. cement. Pulled tubing to 600' and spotted 50 sxs. cement. Pulled tubing to 300' and circulated 185 sxs. cement to the surface..

RECEIVED  
KCC DISTRICT #2

MAY 7 2004

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #18238.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 5-12-04  
INV. NO. 2004061559