

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20119-00-00
Spot: SESW Sec/Twnshp/Rge: 35-20S-7W
660 feet from S Section Line, 1980 feet from W Section Line
Lease Name: WILHAUS Well #: 3 JAN
County: RICE Total Vertical Depth: 3146 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

PROD Size: 5.5 feet: 3405 75 SX CMT
SURF Size: 8.625 feet: 200 150 SX CMT *\$102²⁵*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2004 8:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,355' and top with 5 sxs. cement. Shoot casing off. Pull casing to 1,075' and spot 35 sxs. cement. Pull casing to 600' and spot 35 sxs. cement. Pull casing to 250' and circulate cement to the surface.

RECEIVED
KCC DISTRICT #2
MAY 7 2004

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 04/20/2004 12:00 PM

Witness Type: PARTIAL
KCC Agent: MICHAEL WILSON

WICHITA, KS

Actual Plugging Report:

Perfs:

Sanded to 3,350' and topped with 5 sxs. cement. Shot casing off at 1,127'. Pulled casing to 1,076' and spotted 35 sxs. cement. Pulled casing to 579' and spotted 35 sxs. cement. Pulled casing to 250' and circulated 140 sxs. cement to the surface.

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #18240.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 5-12-04
INV. NO. 2004061559