

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20206-00-01
Spot: W2NENENE Sec/Twnshp/Rge: 35-31S-9W
4920 feet from S Section Line, 500 feet from E Section Line
Lease Name: NEWBERRY Well #: 2
County: HARPER Total Vertical Depth: 4436 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

PROD Size: 5.5 feet: 4427 100 SX CMT
SURF Size: 8.625 feet: 212 225 SX CMT

#144'17

Well Type: SWD UIC Docket No: D19595.0 Date/Time to Plug: 04/21/2004 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perf 2950'-3750' & 4427'-4433'
Plugging 50 sxs & 1300'
Method: 50 sxs & 700'
Circ 270'

RECEIVED
KCC DISTRICT #2

APR 30 2004

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 04/21/2004 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were plugged by pumping 150 lbs of cotton hulls and 50 sacks of cement. SI 400#. Recovered 2000' of 4-1/2" casing. Pulled casing to 1300' and pumped 50 sacks of cement. Pulled casing to 700' and pumped 50 sacks of cement. Pulled casing to 270' and pumped cement to surface with 270 sacks of cement and 100 lbs of cotton hulls.

60/40 posmix with 4% gel.

Perfs:


Top	Bot	Thru	Comments
4427	4433		
2950	3750		

Remarks: ALLIED CEMENT #15165

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 5-12-04

NO. 2004061556