

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21470-00-00
Spot: SESWSE Sec/Twnshp/Rge: 19-32S-7W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MAST Well #: 1-19
County: HARPER Total Vertical Depth: 4500 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 4499 125 SX CMT
SURF Size: 8.625 feet: 251 200 SX CMT

\$ 146²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2004 4:15 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: BRIAN MCCOY Company: QUALITY WELL SERVICE, INC. Phone: (316) 729-9034

Proposed Sand to 4377' & 4 sxs
Plugging 1200' & 35 sxs
Method: 800' & 35 sxs
Circ 300'
Rec 3500'

RECEIVED
KCC DISTRICT #2
MAY 11 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: NONE

Date/Time Plugging Completed: 05/05/2004 4:15 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The perforations were covered with sand from 4377' and capped with 4 sacks of cement. The 4-1/2" casing recovered from 3500' and pulled to 1200' where 35 sacks of cement was spotted. Pulled casing to 800' and spotted 35 sacks of cement. Pulled casing to 300' and circulated cement to surface.

60/40 posmix with 4% gel.


Top	Bot	Thru	Comments
4398	4401		

Remarks: ALLIED CEMENT #15319

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

DATE 5-12-04

INV. NO. 2004061558