

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20050-00-01
Spot: NESE Sec/Twnshp/Rge: 30-32S-7W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: MASNER Well #: 1 OWWO
County: HARPER Total Vertical Depth: 4507 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 4506 175 SX CMT
SURF Size: 8.625 feet: 242 200 SX CMT

48
\$ 146

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2004 1:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: BRIAN MCCOY Company: QUALITY WELL SERVICE, INC. Phone: (316) 729-9034

Proposed Sand to 3337' & 4 sxs
Plugging 1200' & 35 sxs
Method: 800' & 35 sxs
Circ 292'
Rec 3710'

RECEIVED
KCC DISTRICT #2

MAY 11 2004

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: NONE

WICHITA, KS

Date/Time Plugging Completed: 05/04/2004 1:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand from 3337' and capped with 4 sacks of cement. Recovered casing from 3710' and pulled to 1200' where 35 sacks of cement was spotted. Pulled casing to 800' and spotted 35 sacks of cement. Pulled casing to 292' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4416	4420		SPF - NEW
4404	4407		SPF - NEW

Remarks: ACID SERVICE #8269

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 5-12-04

INV. NO. 2004061558