

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21620-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 31-30S-6W  
150 feet from S Section Line, 5130 feet from E Section Line  
Lease Name: CRP MAPLE GROVE Well #: A 1  
County: KINGMAN Total Vertical Depth: 3688 feet

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S. BROADWAY, STE 900  
WICHITA, KS 67202

PKR Size: 4.5 feet: 3688 125 SX CMT  
PROD Size: 4.5 feet: 3688 125 SX CMT  
SURF Size: 8.625 feet: 256 170 SX CMT

*11986*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2004 12:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method:  
Perf 3526'-3530'  
Sand to 3442' & 4 sxs  
1250' & 35 sxs  
850' & 35 sxs  
Circ 320'  
Rec 2985'

RECEIVED  
KCC DISTRICT #2

MAY 11 2004

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/10/2004 1:00 PM

KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were sanded back to 3442' and capped with 4 sacks of cement. The 4-1/2" casing recovered from 2985' and pulled to 1250' where 35 sacks of cement was spotted. Pulled casing to 850' and spotted 35 sacks of cement. Pulled casing to 320' and circulated cement to surface.

60/40 posmix with 4% gel.

**Perfs:**


Top	Bot	Thru	Comments
3526	3636		

Remarks: ALLIED CEMENT #15353

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

**INVOICED**

DATE 5-12-04

INV. NO. 2004061557