

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21327-00-00  
Spot: NESENW Sec/Twnshp/Rge: 15-31S-8W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: STEPHENS A Well #: 3-15  
County: HARPER Total Vertical Depth: 4500 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E. CENTRAL, SUITE 300  
WICHITA, KS 67206

PROD Size: 5.5 feet: 4497 100 SX CMT  
SURF Size: 8.625 feet: 216 175 SX CMT

*SB 14625*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2004 6:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 4416'-4428'  
Plugging 35 sxs 1300'  
Method: 35 sxs 700'  
Circ 270'

RECEIVED  
KCC DISTRICT #2

APR 30 2004

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 04/22/2004 6:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

**Perfs:**

The perforations were sanded back to 4351' and capped with 5 sacks of cement. The casing was recovered from 3000' and pulled to 1300' where 35 sacks of cement was spotted. Pulled casing to 700' and spotted 35 sacks of cement. Pulled casing to 270' and circulated cement with 250 sacks of cement.

60/40 posmix with 4% gel.


Top	Bot	Thru	Comments
4416	4428		

Remarks: ALLIED CEMENT

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

**INVOICED**

DATE 5-12-04

INV. NO. 2004061556