

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01442-00-00  
Spot: W2NWNW Sec/Twnshp/Rge: 7-19S-10W  
990 feet from N Section Line, 330 feet from W Section Line  
Lease Name: KARBER Well #: 1  
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 30681  
Op Name: HOFFMAN OIL, INC.  
Address: 18368 LAWRENCE 2100  
MOUNT VERNON, MO 65712

PROD Size: 5.5 feet: 3349  
SURF Size: 8.625 feet: 169

*\$ 108<sup>88</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2004 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2

MAY 6 2004

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE WICHITA, KS  
Date/Time Plugging Completed: 05/03/2004 7:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded open hole to 3270' and put 5 sacks of cement on top. Perforated at 1250', 900', and 220'. Ran tubing to 1250' and pumped 50 sacks of cement. Pulled tubing to 900' and pumped 50 sacks of cement. Pulled tubing to 220' and circulated cement to surface.

60/40 posmix with 4% gel.

Remarks: ALLIED CEMENT #17929

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

**INVOICED**

DATE 5-12-04

INV. NO. 2004061553