

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21537-00-00
Spot: SWNESW Sec/Twnshp/Rge: 4-20S-10W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BARBER Well #: 2
County: RICE Total Vertical Depth: 3928 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 5.5 feet: 3437 900 SX CMT
SURF Size: 8.625 feet: 209 200 SX CMT

\$127⁶⁶

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 04/29/2004 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (629) 562-8088

Proposed Plugging Method: Sand to 3,380' and top with 5 sxs. cement. Shoot casing off. Pull casing to 1,300' and spot 35 sxs. cement. Pull casing to 900' and spot 35 sxs. cement. Pull casing to 260' and circulate cement to the surface.

RECEIVED
KCC DISTRICT #2
MAY 7 2004

Plugging Proposal Received By: DOUG LOUIS

Witness Type: NONE

WICHITA, KS

Date/Time Plugging Completed: 04/29/2004 2:30 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,320' and topped with 5 sxs. cement. Backside of 5 1/2" casing cemented from 3,437' to the surface. Ran 2 3/8" tubing to 1,300' and spotted 35 sxs. cement w/100# hulls. Pulled tubing to 900' and spotted 35 sxs. cement w/100# hulls. Pulled tubing to 260' and circulated 50 sxs. cement to the surface.

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #14458.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE

5-12-04

WT. NO.

2004061535